

12-16-87

6 061388

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009-20,776 .0001  
NW, SEC. 25, T 20 S, R 15 W/EX

3630 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5591

Lease Name Dueser French Well # 1

Operator: Wes Tech Energy Co Inc.

County Barton 119.60

Name & Address Box 949

Well Total Depth 3680 feet

Great Bend, Ks. 67530

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 876

Abandoned Oil Well X Gas Well Input Well SWD Well U&A

Other well as hereinafter indicated

Plugging Contractor Rockhold Engineering Inc. License Number 5111

Address Box 698 Great Bend, Kansas 67530

Company to plug at: Hour: 9:00AM Day: 16 Month: Dec Year: 19 87

Plugging proposal received from D. B. Pullie

(company name) Rockhold Engineering Inc. (phone) 316-792-2506

were: Order 125 sks 65/35 Pozmix 10% Gel 2% Econolite 5 sks Hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 1:15 PM Day: 16 Month: Dec Year: 19 87

ACTUAL PLUGGING REPORT 8 5/8" set at 876' w/450 sks 5 1/2" set at 3670' w/125 sks.

Top perf at 3628'. Plugged bottom w/sand and 5 sks cement to 3525'. Shot pipe two times and recovered 2750'. Pumped in 8 5/8". 25 sks cement w/5 sks Hulls, in 100' sks cement w/350 Pai.

CONSERVATION DIVISION  
Wichita, Kansas

Remarks: By B. J. Titan  
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

Signed Gilbert G. Scheck  
(TECHNICIAN)

DATE 1-7-88

Gilbert G. Scheck

INV. NO. 19424