

9-22

4-020025

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-009-24,180.0000  
SE SE NW /4 SEC. 25, 20 S, 15 W  
2970 feet from S section line  
2970 feet from E section line

Operator license# 5591  
Operator: Wes Tech Energy Co., Inc.  
Address: P.O. Box 949  
Great Bend, Kansas 67530

Lease: Dueser-French Well # B-1  
County: Barton  
Well total depth 3690 feet 119.92  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 Inch @ 875 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Great Bend Casing Pullers, Inc. License# 4635

Address: P.O. Box 251, Great Bend, Kansas 67530

Company to plug at: Hour: \_\_\_\_\_ Day: 23 Month: September Year: 1993

Plugging proposal received from: Gary Burke

Company: Great Bend Casing Pullers, Inc. Phone: 316/793-9711

Were: 8 1/2" surface casing set @ 875' w/350 sx cmt; 5 1/2" production casing set @ 3688' w/150 sx cmt; Elevation: 1910'; T.D.: 3690'; Anhydrite: 858 - 882'; Salt Section: 1324 - 1649; Perforations: Arbuckle 3632 - 34;

Ordered 170 sx cmt 60/40 pozmix 6% gel w/1/2 # flowcel per sx and 8 sx gel

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[  ], Part[  ], None[  ]

Completed: Hour: 12:00, Day: 22, Month: September, Year: 1993

Actual plugging report: 9/20/93 - sanded off bottom and plugged bottom w/ 5 sx cmt. 9/22/93 - shot off 5 1/2" casing @ 2003'; plugged through 5 1/2" casing; pulled to 1700'; pumped 35 sx cmt and displaced w/ 30 bbls water; pulled to 900'; pumped 45 sx cmt and displaced w/12 bbls water; pulled to 700'; pumped 8 sx gel spacer (in 20 bbls water) followed by wiper plug; pulled to 340'; circ. cmt to surf w/85 sx; pulled remaining casing and filled in the hole w/cmt.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: Allied performed the cementing.  
Condition of casing(in hole):GOOD  BAD  Anhy.plug:YES  NO   
Bottom plug(in place):YES  ,CALC  ,NO  Dakota plug:YES  ,NO   
Plugged through TUBING  , CASING  . Elevation: 1910 GL

SEP 27 1993

CONSERVATION DIVISION  
Wichita, Kansas

I did[  ] / did not[  ] observe the plugging.

Herb Deines  
(agent)

Form CP-2/3

INVOICED  
DATE OCT 05 1993  
INV. NO. 38872