

11-7

6-050092

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-0009-23,546

NE NE NE /4 SEC. 6, 20S, 15 W  
4850 feet from S section line  
330 feet from E section line

Operator license# 4419 Lease SCHULTZ well # 2

Operator: BEAR PETROLEUM County BARTON

Address: Box 438 Well total depth 3840 feet  
Haysville Kansas 67060 Conductor Pipe:        inch @        feet  
Surface pipe 8 5/8 Inch @ 714 feet

124.80

Aband. oil well x, Gas well    , Input well    , SWD    , D & A    

Plugging contractor: Griesel License# 3009

Address: Box 607, Burton, Kansas 67020

Company to plug at: Hour: PM Day: 7 Month: November Year: 1992

Plugging proposal received from: Dick Schremmer

Company: Bear Petroleum phone: 316-524-1225

Were: 8 5/8" set at 714' w 300 sx, backside sq w 150 sx. 5 1/2" set at 3839' w 100 sx. Perfs at 3694'-3695', 3200-3025'. Cast iron bridge plug at 3250'. Run tubing to 3250, pump 150 sx 60/40 poz, 8% gel, pull to 1500', pump 50 sx, circulate cement. Pull tubing to surface and squeeze until standing pressure is above 100#.

Plugging Proposal Received by: Bruce D. Basye  
Plugging operations attended by agent? All[XXX], Part[ ], None[ ]

Completed: Hour: 12:30 PM, Day: 7, Month: November, Year: 1992


Actual plugging report: Plugged as described above. Ran a total of 216 sx 60/40 poz mix 8% gel. Maximum pressure at 450#. Shut in pressure at 450#.

Remarks: BJ Titan on location. Backside squeeze with 150 sx witnessed by Bruce Basye on 19 March, 1992.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 16 1992

I did[XX] / did not[ ] observe the plugging.



Bruce D. Basye  
(agent)  
Form CP-2/3

HA.

**INVOICED**

DATE 11-24-92

INV. NO. 36913