

7-20

4-060751

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,593.0000

SW SW SW /4 SEC. 08, 20 S, 15 W
330 feet from S section line
4950 feet from E section line

Operator license# 5270

Lease: Freeburg Well # 8-13

Operator: K N Energy, Inc.

County: Barton 131.76

Address: P.O. Box 281304
Lakewood, CO 80228-8304

Well total depth 4054 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8% Inch @ 1120 feet

Aband. oil well, Gas well, Input well, SWD, D & A X

Plugging contractor: Allen Drilling License# 5418

Address: P.O. Box 1389 - Great Bend, Kansas 67530

Company to plug at: Hour: A.M. Day: 20 Month: July Year: 1995

Plugging proposal received from:

Company: Phone:

Were: Order 200 sxs 60/40 posmix - 6% gel - 1/4# flocale per sack.
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All [], Part [], None [X]

Completed: Hour: 9:15 A.M. Day: 20 Month: July Year: 1995

Actual plugging report:

- 1st. Plug at 3953' w/25 sxs.
- 2nd. Plug at 1120' w/40 sxs.
- 3rd. Plug at 650' w/100 sxs.
- 4th. Plug at 40' w/10 sxs.
- 15 sxs in Rathole.

RECEIVED
STATE CORPORATION COMMISSION

OCT 6 1995

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Allied Cementing.

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES, CALC, NO Dakota plug: YES X NO

Plugged through TUBING, CASING Elevation: 2076 GL

I did [] / did not [X] observe the plugging.

[Signature]
(agent)

DATE OCT 10 1995

43720