

7-31

4-020067

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 130 SOUTH MARKET, SUITE 2078
 WICHITA, KANSAS 67202

API number: 15-009-24,594-0000

NW NE SE / 4 SEC. 08 , 20 S, 15 W
2310 feet from S section line
990 feet from E section line

Operator license# 05270 Lease: E D & J Well # 8-9

Operator: K N Energy, Inc. County: Barton 130.33
 Address: P.O. Box 281304 Well total depth 4010 feet
Lakewood, CO 80228-8304 Conductor Pipe: 0 inch @ 0 feet
 Surface pipe 8 5/8 Inch @ 645 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allen Drilling Company License# 05418

Address: 1105 Walnut - P.O. Box 1389, Great Bend, KS 67530

Company to plug at: Hour: Day: 31 Month: July Year: 1995

Plugging proposal received from: Mike

Company: Allen Drilling Company Phone: 316-793-5681

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ <u>3875</u> feet with <u>25</u> sacks	Rat hole: <u>15</u> sacks
2nd plug @ <u>1140</u> feet with <u>40</u> sacks	
3rd plug @ <u>645</u> feet with <u>100</u> sacks	
4th plug @ <u>40</u> feet with <u>10</u> sacks	

Plugging Proposal Received by: Ken Kuhn
 Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:30AM, Day: 31, Month: July, Year: 1995

Actual plugging report: Hole reported plugged as above.

RECEIVED
 STATE CORPORATION COMMISSION

Order 195 sx 60/40 pozmix w/ 6% gel and 2.0 sx celloflake or flowcel.

AUG 07 1995

Remarks: Allied Cement Company performed the cement job.

Condition of casing(in hole): GOOD X BAD Any plug: YES X NO

Bottom plug(in place): YES X, CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING X Elevation: 2070 GL

I did / did not X observe the plugging. Ken Kuhn [Signature]
 (agent)

INVOICED
 DATE 8-8-95
 INV. NO. 43255
7-31