

Plugging Abandoned well using K.C.C. Funds

6 070565

6-4-87

API NUMBER 15-009-22,345.0000

162

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

N $\frac{1}{2}$ N $\frac{1}{2}$ SE, SEC. 7, T 20 S, R 15 W/E
2310 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # State Corp. Commission

Lease Name Deckert Well # 1

Operator: Conservation Division

County Barton 123.83

Name & Address: 200 Colorado Derby Bldg.

Well Total Depth 3810 feet

Wichita, Ks.

Conductor Pipe: Size 12 $\frac{1}{2}$ feet U.K.

Surface Casing: Size 8 5/8 feet 1050

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated Paul Ray Williams Jr. (Operator)

Plugging Contractor Great Bend Csg. Pullers and Allied Cmt. License Number

Address P.O. Box 768, Great Bend, Ks. & Box 678 N. 281 Hwy. Great Bend, Ks.

Company to plug at: Hour: 10:00AM Day: 4 Month: June Year: 19 87

Plugging proposal received from Duane Rankin and M. J. Schmidt

(company name) K.C.C. Conservation Division, Wichita (phone) 913-628-1200

were 12 $\frac{1}{2}$ " Conductor (cuc) with N.A., 8 5/8" 1050' S.P. Cuc w/625 sk, 4 $\frac{1}{2}$ " csg set at 3809 W/N.A.

Perfs UK, P.B.T.D. or Bridge at 3590 ft., Sand bottom to 3440 ft.

and 4 sk cement. Shot csg at 3000', 2500', 2200', 2000' and 1700', Recovered 1,711'

Proposal 200 sk 60/40 pozmix 6% gel, 11sk gel and 5 sk hulls. -8 5/8" plug

With pump truck, pump in 8 5/8" csg, 10 sks cmt, 4 sk hull, 100 sk cmt with 1 sk hulls.

11 sk gel, rel plug and 100 sk cmt. Plugging Proposal Received by *Maurice Schmidt* (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 AM Day: 4 Month: June Year: 19 87

ACTUAL PLUGGING REPORT Ordered 200 sk 60/40 pozmix 6% gel, 11sk gel, 5 sk hulls and 8 5/8" wiper plug. Pumped in with pump truck. RECEIVED STATE CORPORATION COMMISSION

Pumped in 2 sk hulls, 100 sk cement, 11 sk gel, JUN 23 1987

Released wiper plug and then 100 sk cement with 1 sk hulls. Added in, Max. pressure

900 P.S.I.G. shut in pressure 650 P.S.I.G. Cemented by Allied Cementing Co. Inc.

Great Bend, Ks.

Remarks: Ran a line in 8 5/8" S.P. to check cement plug. Cement in 8 5/8" S.P. was down only 4 ft.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE

INV. NO.

Signed *Maurice Schmidt* (TECHNICIAN)