

6 070897

2-15

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 009 -24,456.0000  
NE NE SE, SEC. 7, T 20 S, R 15 WXB

TECHNICIAN'S PLUGGING REPORT

Operator License # 5418

2260 feet from S section line  
330 feet from E section line

Operator: Allen Drilling Co.

Lease Name L. Deckert Well # A 1 -7

Name & Address 7950 E. Prentice #100

County Barton 126.75

Englewood, Colorado 80111

Well Total Depth 3900 feet

\* Doug Hoisington

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1063

Abandoned Oil Well Gas Well Input Well SWD Well D&A xx

Other well as hereinafter indicated

Plugging Contractor Allen Drilling Co. License Number

Address 7950 E. Prentice #100 Englewood, Colo 80111

Company to plug at: Hour: AM Day: 15 Month: Feb. Year: 19 91

Plugging proposal received from Craig Christopher

(company name) Allen Drilling (phone) 303-796-7350

were: 8 5/8 1063 ft. s.p. cwc w/375 sks 60/40 poz 2% gel 3% cal cl by Halco.

Arb. at 3718. Elv. 2040; Anhy 1058; No circ problems - 48 visx. 9.7 weight.

Proposal 175 sks 60/40 poz 6% gel 3% cal cl. Spot with drill stem; circ; Spot heavy

mud between all p.plugs. 25 sks at 3620 25 sks at 1060 100 sks at 590 and 10 sks

at 40; 15 sks in rathole, Circ.

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN) xx

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 10:45am Day: 15 Month: Feb. Year: 19 91

ACTUAL PLUGGING REPORT Allen Drilling ordered 175 sks 60/40 poz 6% gel 2%

cal cl. Spotted with drill stem, circ hole; heavy mud between all plugs.

1st plug at 3620 w/25 sks cement

2nd plug at 1060 w/25 sks cement.

3rd plug at 590 w/100 sks cement

4th plug at 40 ft w/10 sks cement 15 sks in rathole (circ)

Remarks: Halliburton Cement (If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 3-11-91

INV. NO. 31100

Signed Marion J. Schmidt (TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 5 1991  
CONSERVATION DIVISION  
Wichita, Kansas