

9-1

To: 1 051201
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 145-21,167-0000
NW SW SW, SEC. 6, T 20 S, R 19 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 4477
Operator: Double T Oil Company
Name:
Address P.O. Box 906
Hooker, OK 73945

990 feet from S section line
4950 feet from E section line
Lease Name Price Well # 2
County Pawnee 143.98
Well Total Depth 4430 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 425

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor McPherson Drilling License Number 5495

Address Route 2, Box 168D, Augusta, KS 67010

Company to plug at: Hour: 10 a.m. Day: 1 Month: 9 Year: 19 89

Plugging proposal received from Bill McPherson

(company name) McPherson Drilling (phone) 316-221-3560

were: 5 1/2" at 4359' Perfs at 4291-95'

1st plug sand back to 4240' and dump 6 sx cement on top of sand through bailer,

2nd plug run tubing to 660' with 60 sx cement,

3rd plug pump 40 sx cement at 440',

4th plug pump 10 sx cement at 40'.

RECEIVED
STATE CORPORATION COMMISSION

SEP - 6 1989

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:45 a.m. Day: 1 Month: 9 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4240' and dumped 6 sx cement on top of sand through bailer,

Spotted plugs through tubing,

2nd plug pumped 4 sx gel and 50 sx cement at 608',

3rd plug pumped 40 sx cement at 428',

4th plug pumped 10 sx cement at 40'.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 660' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-13-89

Signed Richard M. Lacey (TECHNICIAN)

INV. NO. 25886

9-1 NOV 06 1989 FEB 09 1990