

To: 1 010062
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-145-21,235-0000
C W/2 NE, SEC. 6, T 20 S, R 19 W/2
3960 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5652

Lease Name Price Well # 1-6

Operator: Mustang Drilling & Exploration, Inc.
Name & Address: P. O. Box 1609
Great Bend, KS 67530

County Pawnee 142.58
Well Total Depth 4387 Mississippi feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 558

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X _____

Other well as hereinafter indicated _____

Plugging Contractor Mustang Drilling & Exploration, Inc. License Number 5652

Address P. O. Box 1609, Great Bend, KS 67530

Company to plug at: Hour: 8:00 am Day: 5 Month: January Year: 19 86

Plugging proposal received from Mike Campbell

(company name) Mustang (phone) 316-792-7323

were: to fill hole with heavy mud and spot cement through drill pipe Elevation N/A
Anhydrite top 1441'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 30' below the base of the surface pipe with 50 sx cement

3rd plug at 275' with 30 sx cement
solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rat hole with 10 sx cement.

Plugging Proposal Received by Jack L. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X _____

Operations Completed: Hour: 10:30 am Day: 5 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1448' with 50 sx cement, 2nd plug at 558' with 50 sx
cement, 3rd plug at 225' with 30 sx cement, 4th & 5th plugs - solid bridge - hulls - plug
at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10
sx cement.

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan
(if additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

DATE JAN 14 1986

Signed Jack L. Luthi (TECHNICIAN)

INV. NO. 12043

JAN 13 1986

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84

CARD MUST BE TYPED

State of Kansas
NOTICE OF INTENTION TO DRILL
(see rules on reverse side)

CARD MUST BE SIGNED

Starting Date: 12-26-85
month day year

API Number 15- 145-21,235.0000
C W/2 NE Sec 6 Twp 20 S, Rge 19 East West
(location)

OPERATOR: License # 5652
Name Mustang Drilling & Exploration, Inc.
Address P.O. Box 1609
City/State/Zip Great Bend, KS 67530
Contact Person Jim Meroney
Phone 316-792-7323

3960 Ft North from Southeast Corner of Section
1980 Ft West from Southeast Corner of Section
(Note: Locate well on Section Plat on reverse side)

CONTRACTOR: License # 5652
Name Mustang Drilling & Exploration, Inc.
City/State Great Bend, KS 67530

Nearest lease or unit boundary line 1320 feet.
County Pawnee
Lease Name Price Well# 1-6
Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Well Drilled For: Well Class: Type Equipment:
 Oil Swd Infield Mud Rotary
 Gas Inj Pool Ext. Air Rotary
 OWWO Expl Wildcat Cable

Depth to Bottom of fresh water Dakota 250 feet
Lowest usable water formation Cheyenne
Depth to Bottom of usable water 330-550 feet
Surface pipe by Alternate: 1 2
Surface pipe to be set 400-550 feet
Conductor pipe if any required none feet
Ground surface elevation feet MSL.
This Authorization Expires 6-1-86

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth
Projected Total Depth 4375 feet
Projected Formation at TD Mississippi
Expected Producing Formations Cherokee Sand & Miss.

Approved By: 12-4-85
E. Jett/Kostik

I certify that we will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to K.C.C. specifications.

Date 12-3-85 Signature of Operator or Agent Title Exploration Manager

Form C-1 4/84

Mood in 12-29-85 550' - 8 5/8 No

Base Anky - 50 SX
SP + 30 - 50 SX
SP 275 - 30 SX 60/40 - 6%
SB - 40' - 1H - 10 SX
Rat - 10 SX

STATE CORPORATION COMMISSION

JAN 13 1986

CONSERVATION DIVISION
Wichita, Kansas