

6 062429

6-6  
API NUMBER 15- 009-24-357-0000

151  
W/E

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NW, SEC. 24, T 20 S, R 14  
4290 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408

Lease Name Titus Well # 2

Operator: Trans Pacific Oil Corp.  
Name & Address #410 One Main Place  
Wichita, Kansas 67202

County Barton 117.00  
Well Total Depth 3600 - PB 3300 feet  
Conductor Pipe: Size feet  
Surface Casing: Size 8 5/8" feet 409'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address Box 347, Chase, Kansas 67524

Company to plug at: Hour: 9:00 A.M. Day: 6 Month: June Year: 19 91

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: Order 300 sks. 60/40 posmix, - 8% Gel. - 5 sks. hulls.

Plugging Proposal Received by Gilbert G. Scheck  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 2:30 P.M. Day: 6 Month: June Year: 19 91

ACTUAL PLUGGING REPORT 8 5/8" set at 409' w/200 sks. 4 1/2" set at 3599' w/175 sks.

Top perf at 3260'. Plugged bottom with sand and 4 sks. cement to 3200'.

Shot pipe 5 times and recovered 1900'. Pumped in 4 1/2" casing and circulated cement from 800' to surface. Pulled all casing. Hooked on to 8 5/8" and squeezed cement to 400 P.S.I. - used 300 sks. cement.

RECEIVED  
STATE CORPORATION COMMISSION

Remarks: By Allied Ran Line to 3000'  
(If additional description is necessary, use BACK of this form.)

JUN 17 1991

INVOICED  
DATE 7-8-91  
INV. NO. 32260  
6-6

Signed [Signature] (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas  
E.A.H.