

4-032113

11-10

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-009-24,356.0000

SW NW NE /4 SEC. 24, 20, 14 W
4290 feet from S section line
2310 feet from E section line

Operator license# 6170

Lease: Titus Well # 1

Operator: Globe Operating, Inc.

County: Barton

Address: P.O. Box 12
Great Bend, Kansas 67530

Well total depth 3600 ^{117.00} feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 254 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Mike's Testing & Salvage, Inc. License# 31529

Address: Chase, Kansas 67525

Company to plug at: Hour: A.M. Day: 10 Month: November Year: 1995

Plugging proposal received from: Mike Kelso

Company: Mike' Testing & Salvage, Inc.

Were: Order 300 sxs 60/40 pozmix - 10% gel - 400# hulls.
Allied Cement Company.

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1995 11-29-1995
CONSERVATION DIVISION

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 A.M., Day: 10, Month: November, Year: 1995

Actual plugging report: 8 5/8" set at 254' cwc with 150 sxs. 5 1/2" set at 3585' with 150sxs. Prod. Perfs 3377' - 3529'. Squeezed at 791' with 180 sxs cwc. Critical area control shot at 1400'. Squeezed 5 1/2" with 300 sxs cement blend with 400# hulls to Max. P.S.I. 500#. Close in P.S.I. 100#. Test 8 5/8" to 500#. Full to surface. Plug complete.

Remarks: Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES, CALC, NO Dakota plug: YES, NO
Plugged through TUBING, CASING. Elevation: GL

Failed did not observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE NOV 30 1995
INV. NO. 44161
11-10