

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.009.01541.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1964

CONSERVATION DIVISION
Wichita, Kansas

4-29-1964

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Woody Roberts of Woody's Quality Oil Co. has this date requested permission to plug the following described well:

Mr. Woody's Quality Oil guarantees payment of the plugging fee.

Operator's full Name: Woody's Quality Oil Company

Complete Address: 914 Gravens Bldg., Oklahoma City,
Oklahoma

Lease Name: Penner Well No. # 1

Location: SW NE SW Sec. 12 Twp. 20 Rge. 15 (E) (W) W

County Barton Total Depth 3818 Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. D. B. Pully was instructed to plug the well as follows:

8 5/8" 864' Cwc. Well flowing salt water.

Sanded hole back to 3350' & dumped 5 sax cement with
dump bailer. Pulled pipe. Squeezed well with 20 sax mud
& 100 sax cement with pump truck, cementing from 320' to
base of cellar.

Very truly yours,

Don Pully