



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas, and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Junior Gates of Clinton Oil Company has this date requested permission to plug the following described well:

Mr. Clinton Oil Company guarantees payment of the plugging fee.

Operator's full Name: Clinton Oil Company

Complete Address: 217 N. Water, Wichita, Kansas 67202

Lease Name: Esther V. Unruh Well No. # 1

Location: NE NE SE Sec. 25 Twp. 20 Rge. 15 (E)(W) W

County: Barton Total Depth 3640' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Darrell Kelso was instructed to plug the well as follows:

8 5/8" 871' Cwc. Perf. 3633'.

Sanded hole back to 3600' & dumped 5 sax cement with dump bailer.

Pulled pipe, Mud to 375', set 25' rock bridge, & displaced 5 yds.

Ready-mix Cement, cementing from 350' to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent