

State of Kansas



15.009.20776.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

JAN 18 1974

CONSERVATION DIVISION
Wichita, KansasJ. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Leonard Williamson of Duke Drilling Company has this
date requested permission to plug the following described well:Mr. Icer Addis guarantees payment of the plugging fee.Operator's full Name: Icer AddisComplete Address: Box 8038, Wichita, KansasLease Name: Dueser Well No. # 1Location: NE SE NW Sec. 25 Twp. 20 Rge. 15 (E)(W) WCounty: Barton Total Depth 3643 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Leonard Williamson was instructed to plug the well as follows:8 5/8" csg. 876' Cwc. Set in Anhy.Circulated hole with heavy mud to 400', set plug, & displaced 30 saxcement thru drill pipe. Mud to 40', 1/2 sax hulls, plug, & displaced10 sax cement, cementing to base of cellar.

Very truly yours,

 Conservation Division Agent