


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Ness County, Sec. 14 Twp. 20S Rge. 24W (E) (W)
Location as "NE/CNW/SW" or footage from lines SE SW SE



Locate well correctly on above
Section Plat

Lease Owner Meltzer Oil Company
Lease Name Petersilie Well No. A-#6
Office Address P. O. Drawer B, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 7-17-66 19
Application for plugging filed 7-17-66 19
Application for plugging approved 7-17-66 19
Plugging commenced 7-17-66 19
Plugging completed: 7-17-66 19

Reason for abandonment of well or producing formation Surf. pipe parted, hole lost
so plugged, abandoned, and skidded rig 10' East

If a producing well is abandoned, date of last production - 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Leo Massey, Hays, Kansas
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 1342 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	286'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

surface pipe collapsed @ 30', cemented with 60 sacks cement through
1 joint of drill pipe to cellar bottom by Globe Cementing
Job Completed @ 3:00 a.m. 7-17-66 under orders of Leo Massey, Hays, Ks.

FILED
STATE CORPORATION COMMISSION
JUL 29 1966
CONSERVATION DIVISION
WICHITA, KANSAS
7-29-1966

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Leben Drilling, Inc.
Address Box 486, Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF BARTON, ss.
Doug Boyd (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Doug Boyd
Box 486, Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN TO before me this 28th day of July, 19 66
Wanda Nichols
Notary Public.

My commission expires April 1, 1967

DRILLER'S LOG

COMPANY: Meltzer Oil Company
 CONTRACTOR: LEBEN DRILLING, INC.
 FARM: PETERSILIE A-#6
 LOCATION: SE SW SE SEC. 14-20S-24W
 NESS COUNTY, KANSAS
 COMMENCED: 7-13-66
 COMPLETED: 7-17-66 (Skidded Rig)

0	130	Shale, Sand
130	375	Shale
375	900	Shale, Redbed
900	920	Hard Sand
920	1165	Sand, Redbed
1165	1342	Redbed
	<u>1342</u>	<u>RTD</u> - Plugged & Abandoned Hole, Skidded Rig

Set 20# used surface casing @ 286' cemented with 190 sacks Common 2% cc. Surface Pipe parted and hole was lost, plugged and abandoned and skidded rig 10' East on 7-17-66 to drill new hole

I, Doug Boyd, do hereby certify that the above and foregoing is a true and correct copy of the log of the Petersilie A-#6 well, located SE SW SE of Section 14, Township 20 South, Range 24 West, Ness County, Kansas, as reflected by the records of Leben Drilling, Inc.

Doug Boyd
 Doug Boyd

STATE OF KANSAS)
) SS
 COUNTY OF BARTON)

Subscribed and sworn to and before me, a Notary Public, in and for Barton County, Kansas, this 28th day of July, 1966.

Ulanda Nichols
 Ulanda Nichols

My Commission Expires:
 April 1, 1967

RECEIVED
 STATE CORPORATION COMMISSION
 JUL 29 1966