

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15.135.00669.0000

API NUMBER 6/27/58

LEASE NAME Petersilie B #1

WELL NUMBER #1

2970 Ft. from S Section Line

2970 Ft. from E Section Line

SEC. 14 TWP. 20 RGE. 24W (E) or (W)

COUNTY Ness

Date Well Completed 6/27/58

Plugging Commenced 2/12/96

Plugging Completed 2/12/96

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Joe Gerstner Oil Co.

ADDRESS RR 1, Box 115A, Ness City, Ks. 67560

PHONE# (913) 798-2893 OPERATORS LICENSE NO. 9615

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2/12/96 (date)

by Kevin Strube (KCC District Agent's Name).

Is ACO-1 filed? NAs If not, is well log attached? \_\_\_\_\_

Producing Formation Mississippian Depth to Top 4435' Bottom 4457' T.D. 4457'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Mississippian				5 1/2"	4440	None
				8 5/8"	356'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set.

1st plug pumped down 5 1/2" with 300 lbs. hulls, 25 sx cement, 25 sx gel, and 85 sx cement.  
Maximum pressure 800 psi and shut in 500 psi. 2nd plug pumped 50 sx cement down 8 5/8"  
x 5 1/2" Maximum pressure 300 psi and shut in 100 psi.  
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Allied License No. \_\_\_\_\_

Address \_\_\_\_\_

RECEIVED  
KANSAS CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Joe Gerstner Oil

STATE OF Kansas COUNTY OF Ness, ss.

APR 08 1996  
4-8-1996

Joe Gerstner (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Joe Gerstner

(Address) RR1 Box 115A, Ness City, Ks. 67560

SUBSCRIBED AND SWORN TO before me this 5th day of April, 19 96

Karen Stoecklein  
Notary Public



COMPANY:  
CONTRACTOR:  
FARM:  
LOCATION:  
COMMENCED:  
COMPLETED:

KAMAC OIL & GAS CORP. & LEBEN DRILLING, INC.  
LEBEN DRILLING, INC.  
W. H. PETERSILIE #1  
SE $\frac{1}{4}$  SE $\frac{1}{4}$  NW $\frac{1}{4}$  SEC. 14-20S-24W  
NESS COUNTY, KANSAS  
MAY 7, 1958  
MAY 23, 1958

0	275	Soil, Sandy clay & Shale		
275	355	Shale		
355	770	Shale & Redbed		
770	915	Redbed		
915	965	Anhydrite		
965	1360	Redbed, Shale & Sand		
1360	1985	Redbed & Shale	Heebner	3711
1985	2275	Shale	Toronto	3728
2275	3150	Shale & Lime	Lansing	3758
3150	3285	Shale	Marmaton	4206
3285	3705	Shale & Lime	Ft. Scott	4279
3705	3910	Lime	Cherokee	4305
3910	4160	Lime	Cherty Cong.	4370
4160	4333	Lime & Shale	Miss. Dolo.	4399
4333	4365	Lime	RTD	4457
4365	4402	Lime & Chert	Elevation	2320
4402	4427	Chert & Lime		
4427	4457	Dolomite		
	4457	Rotary Total Depth		

LOG TOPS:

Set 356' of 8 5/8" surface casing w/200 sacks cement & 4 sacks CaCl.

I, Frank Hamlin, do hereby certify that the above and foregoing is a true and correct copy of the log of the W. H. Petersilie #1, SE $\frac{1}{4}$  SE $\frac{1}{4}$  NW $\frac{1}{4}$  of Section 14, Township 20 South, Range 24 West, Ness County, Kansas, as reflected by the files of Leben Drilling, Inc.

LEBEN DRILLING, INC. (CORP.)  
CONSERVATION DIVISION  
Wichita, Kansas

*Frank Hamlin*  
Frank Hamlin

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 3rd day of June, 1958.

*Ruth N. Benjamin*  
Ruth N. Benjamin - Notary Public