

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

OR

FORMATION PLUGGING RECORD

Strike out upper line when reporting plugging of formations.

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Barton County, Sec. 12 Twp. 20 Rge. 15W. (E) (W)

Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines SW SE SW

Lease Owner Kansas-Nebraska Natural Gas Co., Inc.

Lease Name E. W. Schultz Well No. 1

Office Address Hastings, Nebraska

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 8-28-51 19

Application for plugging filed 8-28-51 19

Application for plugging approved 8-28-51 (verbal) 9-4-51 (written) 19

Plugging commenced 8-28-51 19

Plugging completed 8-29-51 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C. D. Stough, Box 207, Great Bend, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3725' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Sand, Shale, and shells	Surface Water	40'	500'	8-5/8"	8-17-51	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

From total depth of 3725' to 250' filled with heavy rotary mud.  
Halliburton 8-5/8" plug was set at 250' followed by 15 sacks of cement thru the drill pipe.  
Filled from there to 40' with heavy rotary mud.  
Another Halliburton 8-5/8" plug set at 40' and filled from there to bottom of cellar with 10 sacks of cement.

RECEIVED  
OCT 3 1951  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to Kansas-Nebraska Natural Gas Co., Inc.  
Address Hastings, Nebraska

STATE OF Kansas, COUNTY OF Barton, ss.  
Thomas C. Swanson (employee of owner)

being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Thomas C. Swanson*

Box 127, Pawnee Rock, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2 day of Oct. 1951

My commission expires 2-13-1953

22-2625 2-48-15M

PLUGGING  
FILE SEC 12 T 20 R 15W  
BOOK PAGE 107 LINE 9

KANSAS-NEBRASKA NATURAL GAS CO., INC.  
 300 North St. Joseph St.,  
 Hastings, Nebraska

Schultz #1

Commenced R.D. 8/14/51  
 Completed R.D. 8/28/51  
 Total Depth: 3725'  
 Casing Record: 936' of 8 5/8"

SW-SE-SW  
 Sec. 12-20-15  
 Barton County, Kansas  
 Elevation:  
 Initial Prod:  
 Contractor: Buick Drilling  
 Inc.

Strata	Depth
Clay & Sand	0 - 40'
Sand & Shale	40 - 180
Shale & Shells	180 - 335
Sand & Shale	335 - 470
Shale	470 - 500
Red Bed	500 - 918
Gyp	918 - 926
Anhydrite	926 - 960
Shale & Shells	960 - 1895
Lime & Shale	1895 - 3145
Broken Lime	3145 - 3300
Lime Shale	3300 - 3425
Lime	3425 - 3593
Conglomerate	3593 - 3672
Lime	3672 - 3725

I hereby certify the above a true and correct drilling log as reflected by the Daily Drilling reports of the Buick Drilling Inc.

BUICK DRILLING INC.  
 OCT 3 1951  
 CONFIDENTIAL DIVISION  
*H. R. Buick*  
 H. R. Buick Pres.

Signed and sworn to in my presence this 30th day of August, 1951, by H. R. Buick, President of the Buick Drilling Inc.

*Hubert Brock*  
 Notary Public

My Commission Expires: August 2, 1955.

**PLUGGING**  
 FILE SEC. 187.20R(50)  
 BOOK PAGE 107 LINE 9