

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-23,673.0000

LEASE NAME Miller

WELL NUMBER #1

660 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 22 TWP. 20 RGE. 15 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 12-26-90

Plugging Completed 1-29-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Dunne Equities, Inc.

ADDRESS 8100 E. 22nd St. North, Bldg. 1110, Wichita

PHONE# 616-685-4467 OPERATORS LICENSE NO. 6149

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on December 26, 1989 (date)

by Herb Deines (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3757'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	709'	None
				5-1/2"	3755'	1,947.00'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3620' and 5 sacks cement. Shot casing at 2900', 2600', 2200', and 1950'. Pulled 50 joints of 5-1/2" casing. Allied plugged well with 25 sacks cement and 500 hulls blended in 175 sacks 60/40 pozmix cement with 8% gel. Maximum pressure was 500 psi and shutin 400 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. RECEIVED 111

Address Box 698, Gt. Bend, Ks. 67530 STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Dunne Equities, Inc. JAN 30 1990

STATE OF Kansas COUNTY OF Barton, ss. CONSERVATION DIVISION
 Wichita, Kansas

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 29th day of January, 1990

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91

My Commission Expires: