

STATE OF KANSAS
STATE CORPORATION COMMISSION
D. S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15.009.20671.0001

API NUMBER 15-009-20,6718

LEASE NAME Smith

WELL NUMBER #1

RECEIVED
KANSAS CORP. CO.
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 19 TWP. 20S RGE. 15W (E) or (W)

COUNTY Barton

LEASE OPERATOR John H. Shaida

ADDRESS 4126 N. Sweet Bay Circle Wichita, Ks. 67226

PHONE (316) 636-2525 OPERATORS LICENSE NO. 3833

Date Well Completed _____

Character of Well Oil

Plugging Commenced 6-8-98

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 6-10-98

The plugging proposal was approved on _____ (date)

by Bruce Bayse (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3944'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1132'	None
				5-1/2"	3941'	2000'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs are used, state the character of same and depth placed, from _____ feet to _____ feet each section. Plugged off bottom with sand to 3823' and 5 sks. cement. Shot pipe @ 3000', 2600', 2400', 2300', 2200', 2000', pulled up to 1950', pumped 135 sks. cement w/300# hulls, pulled up to 1175', pumped 40 sks. cement w/100# hulls, pulled to 725', pumped 35 sks. cement, pulled to 200' and circulated 40 sks. cement. 60/40 pos. 10% gel.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

Name of Party Responsible for Plugging Fees: _____

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS. 67524

SUBSCRIBED AND SWORN TO before me this 17th day of June, 19 98

[Signature]
Notary Public

My Commission Expires: _____

