

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-24,409.0000

LEASE NAME Smith

WELL NUMBER #1

2310 Ft. from S Section Line

1490 Ft. from E Section Line

SEC. 19 TWP. 20 RGE. 15 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 10-18-90

Plugging Completed 10-30-90

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Woodman-Iannitti Oil Co.

ADDRESS Box 308, Great Bend, Ks. 67530

PHONE# (316) 792-1922 OPERATORS LICENSE NO. 6588

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-30-90 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3935'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	1121'	None
				5-1/2"	3931'	2750.05'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3650' and 5 sacks cement. Shot casing at 2939', 2813', & 2723'. Pulled 78 joints of 5-1/2" casing. B.J. Services plugged well with 500# hulls and 200 sack 60/40 pozmix with 8% gel. Maximum pressure was 1000 psi and shutin 700 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Woodman-Iannitti Oil Co.

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

NOV 1 1990
 11-1-1990
 CONSERVATION DIVISION
 STATE CORPORATION COMMISSION
 KANSAS

(Signature) James W. Rockhold
 James W. Rockhold
 (Address) Box 698, Great Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 31st day of October, 1990

Louise M. Leatherman
 Notary Public

My Commission Expires:

STATE NOTARY PUBLIC
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91