

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Building  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

#4

API NUMBER 15-009-22902-0000

LEASE NAME Unruh

WELL NUMBER "C" #1

4290 Ft. from S Section Line

4950 Ft. from E Section Line

SEC. 26 TWP. 20 RGE. 15 (E) or (W)

COUNTY Barton

Date Well Completed \_\_\_\_\_

Plugging Commenced 11-13-89

Plugging Completed 11-27-89

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days.

LEASE OPERATOR Palomino Petroleum

ADDRESS Rt. #5, Box 51-C, Newton, Ks. 67114

PHONE # 816-283-0232 OPERATORS LICENSE NO. 5161

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on November 13, 1989 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? \_\_\_\_\_ If not, is well log attached? With application

Producing Formation \_\_\_\_\_ Depth to Top \_\_\_\_\_ Bottom T.D. 3710'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	912'	None
				5-1/2"	3700'	2,203.35'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet, each set. Dumped sand to 3461' and 5 sacks cement. Shot casing at 3050, 2800, 2500' and 2200'. Pulled 70 joints of 5-1/2" casing; Howco plugged well with 500# hulls and 200 sacks 60/40 pozmix with 8% gel. Maximum pressure was 850 psi and shutin 450 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Kansas 67530

RECEIVED  
STATE CORPORATION COMMISSION

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum NOV 28 1989

STATE OF Kansas COUNTY OF Barton, ss. \_\_\_\_\_

James W. Rockhold

(Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold  
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of November, 19 89

STATE NOTARY PUBLIC  
IONA M. LEATHERMAN  
Barton County, Kansas  
My Appt. Exp. 9-26-91

Iona M. Leatherman  
Notary Public

My Commission Expires \_\_\_\_\_