

#4

API NUMBER 15-009-22613.0000

LEASE NAME Unruh

WELL NUMBER "B" #1

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

3630 Ft. from S Section Line

4950 Ft. from E Section Line

LEASE OPERATOR Palomino Petroleum

SEC. 26 TWP. 20 RGE. 15 (E) or (W)

ADDRESS Rt #5, Box 51-C-Newton, Kansas 67114

COUNTY Barton

PHONE# 816-283-0232 OPERATORS LICENSE NO. 5161

Date Well Completed _____

Character of Well oil

Plugging Commenced 11-18-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 11-27-89

The plugging proposal was approved on November 13, 1989 (date)

by Gilbert Scheck (KCC District Agent's Name).

Is ACO-1 filed? _____ If not, Is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3735'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	912'	None
				5-1/2"	3700'	3,090.75'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3600' and 5 sacks cement. Shot casing at 3100'. Pulled 87 joints of 5-1/2" casing. Howco plugged well with 500# hulls and 200 sacks 60/40 pozmix cement with 8% gel. Maximum pressure was 900 psi and shutin 650 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Gt. Bend, Ks. 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Palomino Petroleum

STATE OF Kansas COUNTY OF Barton, ss.


James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 27th day of November, 1989

My Commission Expires:



Notary Public