

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
200 Colorado Derby Bldg.  
Wichita, Kansas 67202

Form CP-4  
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit

COUNTY Barton SEC. 26 TWP. 20 RGE. 15w E/W  
Location as in quarters or footage from lines:  
SW SW SW


Lease Owner D.R. Lauck Oil Co. Inc.  
Lease Name Schultz #1 Well No. \_\_\_\_\_  
Office Address 221 S. Broadway, Suite 400, Wichita, Ks 67202  
Character of Well (Completed as Oil, Gas or Dry Hole): \_\_\_\_\_  
Date Well Completed \_\_\_\_\_  
Application for plugging filed \_\_\_\_\_  
Plugging commenced 2/8/83  
Plugging completed 3/8/83  
Reason for abandonment of well or producing formation  
Depleted

Locate Well  
correctly on above  
Section Platt.

Was permission obtained from the Conservation Division or it's  
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Gilbert Scheck  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ bottom \_\_\_\_\_ T.D. 3672'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	916'	none
				5 1/2"	3663 1/2"	2891'

Describe in detail the manner in which the well was plugged, indicating where the mud  
fluid was placed and the method or methods used in introducing it into the hold. If cement  
or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet  
to \_\_\_\_\_ feet for each plug set.

Plugged bottom with 5 sacks cement, sand to 3610' & ran 5 sacks cement.  
Shot casing at 3100' & 2917'. Pulled total of 93 joints.. Plugged well  
with 4 hulls, 12 gel, 65 cement, 3 gel, 1 hull, plug, & 100 sacks 50/50  
pos. 4% gel 3% c.c.

Plugging complete

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Kelso Casing Pulling

STATE OF Kansas COUNTY OF Rice, ss.  
R. Darrell Kelso (employee of owner) or (owner or operator) of the  
above-described well, being first duly sworn on oath, says: That I have knowledge of the  
facts, statements, and matters herein contained and the log of the above-described well as  
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso  
Box 347, Chase, Ks. 67524  
(Address)

SUBSCRIBED AND SWORN TO before me this 8th day of March, 1983

My Commission expires:



Irene Hoover  
STATE CORPORATION COMMISSION  
Notary Public.

MAR 14 1983

CONSERVATION DIVISION  
Wichita, Kansas

3-14-1983

D. R. Lauck Oil Company, Inc. -  
 221 S. Broadway, Suite 400  
 Wichita, Kansas 67202

Schultz #1  
 SW SW NW Sec. 26-20S-15W  
 Barton County, Kansas

Contractor: D. R. Lauck Oil Company, Inc.  
 221 S. Broadway, Suite 400  
 Wichita, Kansas 67202

Commenced: April 3, 1981  
 Completed: April 9, 1981

RECEIVED  
 STATE CORPORATION COMMISSION

NOV 16 1982

CONSERVATION DIVISION  
 Wichita, Kansas

Drillers Log

Sand & Top Soil	200
Blue Shale	320
Dakota Sand	435
Red Bed	919
Shale & Shells	1145
Red Bed & Shale	1940
Shale & Shells	3130
Lime & Shale	3530
Lime	3666 RTD

Casing: 916' 8-5/8" cemented with 425 sacks 60-40 Pozmix Cement,  
 2% Gel, 3% CaCl<sub>2</sub>.

3663-1/2' 5-1/2" cemented with 100 sacks 60-40 Pozmix  
 salt saturated cement, 8# Gilsonite per sack,  
 3/4 of 1% FRA, 5 sacks salt flush.