

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barton County. Sec. 20 Twp. 20S Rge. 15 (W)

Location as "NE/CNW/SW" or footage from lines C-NW-SE-NW

Lease Owner Sunray Oil Corporation

Lease Name Unruh Well No. 1

Office Address Box 195, Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed September 13 19 53

Application for plugging filed September 15 19 53

Application for plugging approved September 16 19 53


Plugging commenced September 13 19 53

Plugging completed September 13 19 53

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Name of Conservation Agent who supervised plugging of this well C. D. Strough, Great Bend, Kansas

Producing formation Arbuckle Depth to top 3833 Bottom 3925 Total Depth of Well 3925 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3400		8 5/8	1096	None
Toronto		3417				
Tatan		3487				
Lansing-KC		3501	3728			
Conglomerate		3765				
Arbuckle	Water	3833	3925			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

RTD 3925'. Mudded hole to 300' and ran 30 sax cement. Mudded hole to 60' and ran 20 sax cement. Dry hole plugged and abandoned under the supervision of commission representative.

Well log attached.

9-30-1953
RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1953
CONSERVATION
Wichita, Kan.

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Stickle Drilling Company
Address Philtower Building, Tulsa, Oklahoma

STATE OF KANSAS COUNTY OF BARTON
Robert K. Crouch (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.
(Signature) Robert K. Crouch
Box 195, Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of September, 19 53

My commission expires December 24, 1956 Notary Public.

PLUGGING
FILE SEC 20 120 154
BOOK PAGE 128 LINE 42

Sunray Oil Corporation
Tulsa, Oklahoma

Tulsa, Oklahoma
September 18, 1953

CONTRACTOR: Stickle Drilling Company
Drilling Commenced: August 27, 1953
Drilling Completed: September 13, 1953

S. Unruh #1 NW-SE-NW-
Section 20-20S-15W,
Barton County, Kansas.

DRILLERS LOG

Surface Clay	0-70
Shale & Shells	70-415
Shale	415-465
Sand	465-545
Sand-Shale & Shells	545-750
Shale & Red Bed	750-985
Red Bed	985-1090
Anhydrite	1090-1100
Shale & Sand	1100-1530
Shale & Shells	1530-1805
Shale & Lime	1805-2115
Lime & Shale	2115-2310
Shale & Lime	2310-3115
Lime & Shale	3115-3370
Shale & Lime	3370-3490
Lime	3490-3610
Lime & Shale	3610-3660
Lime	3660-3759
Lime & Shale	3759-3788
Conglomerate	3788-3840
Arbuckle	3840-3925 TD

I, Frank E. Stickle hereby certify the above to be a true and complete Drillers Log of the Sunray Oil Corporation's S. Unruh #1 NW-SE-NW-Section 20-20S-15W, Barton County, Kansas.

Frank E. Stickle
Frank E. Stickle

Edward L. Beckel
Notary Public

June 26, 1953
My Commission Expires

RECEIVED
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 20-20S-15W
BOOK PAGE 128 LINE 42