

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 17-17

LOCATION NW-NW-5W

SEC. 5 TWP. 20 RGE. 15 W

Dry Hole _____ Abandoned Oil Well Abandoned Gas Well _____

I have this date completed supervision of plugging of:

Well No. 1 Lease Ben Smith

Operator Martin Wunderlich Address To Geo W. Newman
Box 39 Chase, Kans

Field _____ County Barton Co.

Total Depth 3730 Feet.

Plugging Contractor R.E.S. Pipe Pulling Co.

Plugging Contractor's License No. 1

Address Box 192 Ellinwood Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 5/8" @ 998' C.W.C. Oil string 5 1/2"
O.D. @ 3704' wt 12.5 sk Cem. Sanded hole
back to 3690' and dumped 5 sk Cem. Shot
off and pulled 5 1/2" casing. Filled with mud
to 300' at rock bridge. and run 20 sk 4
Cem. with dump basin. Mud to 35' r. bridge
and 10 sk mixed Cem to surface.

PLUGGING
FILE SEC 5 T 20 R 15 W
BOOK PAGE 17 LINE 17

RECEIVED
STATE CORPORATION COMMISSION
MAR 23 1954
CONSERVATION DIVISION
Wichita, Kansas

Warren H. Horner
District Conservation Agent
Date Mar 20, 1954

3-23-1954