



DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 66-5

LOCATION NE-NE-22W

SEC. 6 TWP. 20 RGE. 15

Dry Hole \_\_\_\_\_ Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 2 Lease A. Dicks

Operator The Texas Company Address Box #1801 - Wichita - Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3752 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2 - 1008 ft. Circulated with cement -  
5 1/2" casing set at 3752 - Plugged back from bottom  
to 3415 ft. Dumped 5 sacks of cement to the 5 1/2" casing  
at 3415 ft. Shot off & Pulled 5 1/2" casing - Filled with  
mud to 2500 ft. Set Bridge & 15 sacks cement at 2500 ft -  
Mud to 36 ft. Bridge & 10 sacks cement at the surface -  
The Chase Pulling Co - Contractors

RECEIVED

Conservation Div. C. H. Stovall  
District Conservation Agent

NOV 12 1948

STATE CORPORATION Date 11-8-48  
COMMISSION

KANSAS

11-12-1948

PLUGGING  
FILE REC-6-T-20-R-5  
BOOK FILE-66-5