

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

7-21-1957

Operator's Full Name Drillers-Producers Pipe & Supply, Inc.

Complete Address: Box 368, Great Bend, Kansas 67530

Lease Name Douglas Well No. # 1

Location NW NE NW Sec. 12 Twp. 20 Rge. 15 (E) (W) W

County Barton Total Depth 3993

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Southwest Casing Pulling Company, Inc.

Address: Box 364, Great Bend, Kansas License No. # 399

Operation Completed: Hour 11:45AM Day 19 Month 6 Year 1967

The Above well was plugged as follows:

8 5/8" 913' Cwc.

Sanded hole back to 3400' & dumped 4 sax cement with dump bailer. Pulled pipe.

Mud to 400', set 25' rock bridge, & displaced 5 yds. ready-mix cement, cementing from 375' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don Truman
Well Plugging Supervisor

DATE 6/22/67

INV. NO. 5437-u