

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 5-38

LOCATION NE-NE-SW

SEC. 22 TWP. 20 RGE. 15

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Bondurant

Operator Cities Serv. Oil Co. Address Box 751 Great Bend Kans.

Field \_\_\_\_\_ County Barton

Total Depth 3729 Feet.

Plugging Contractor B & W Casing Pulling Co

Plugging Contractor's License No. 17

Address Great Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 7/8" @ 882' C.W.C. Oil String 5 1/2" O.D.  
@ 3729 w/ 200 SX Ceme. 4 W.P. 3691' Top Perf 3654' Filled  
back with sand from 3691' to 3650' and dumped 5  
sf Ceme. shot off and pulled approx 1900' of 5 1/2"  
Casing. Filled with heavy mud to 300' set rock  
bridge and mixed and run 20 SX of Ceme. mud to  
35' rock bridge and 10 SX Ceme. to base of cellar

STATE OF KANSAS  
JAN 21 1954

Warren H. Warner  
District Conservation Agent

Date 1-18-54

**PLUGGING**  
FILE SEC 22 T 20 R 15  
BOOK PAGE 5 LINE 38

1-21-1954