

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 63-43

LOCATION SE SE 21E

SEC. 22 TWP. 20 RGE. 15-W

Dry Hole        Abandoned Oil Well        Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 1 Lease Hattie Urwick

Operator Haus. Nebraska Natural Gas Address Hastings - Nebraska

Field        County Barton

Total Depth 3715 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 744 ft. Circulated with cement.  
4 1/2" casing set at 3715 ft. Cemented with 100 sacks cement  
Plugged back to 3650 ft with gravel - Dumped 3 sacks  
of cement at 3650 ft. Shot & pulled the casing  
back to 250 ft. Set back bridge x 15 sacks of  
cement at 250 ft. Used to 30 ft. Plug &  
10 sacks of cement at the surface  
Frank Carroll - Plugging Contractor

RECEIVED  
STATE CORPORATION COMMISSION  
MAR - 9 1951  
CONSERVATION DIVISION  
Wichita, Kansas  
District Conservation Agent

Date 3-7-51

**PLUGGING**  
FILE SEC 22 TWP 20 RGE 15W  
PAGE 43