

DISTRICT CONSERVATION AGENT'S REPORT

B

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 67-2

LOCATION G5/2-S/2-NE/4

SEC. 22 TWP. 20 RGE. 15-w

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No. 2 Lease Wurub

Operator Haus-Web. Nat'l Gas Co. Inc. Address Box # 127 - Pawnee Rock, Kans.

Field _____ County Barton

Total Depth 3718 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 5/8 - 970 ft. Circulated with cement
5 1/2" casing set at 3714 ft. - 100 sacks of cement
Plugged back to 3680 ft with sand - dumped 8 sacks
of cement at 3680 ft - Shot off & pulled the 5 1/2" casing
and to 250 ft. Set 400 lb bridge & 10 sacks of
cement at 250 ft. and to 35 ft. Plug & 10 sacks of
cement at the surface.

Frank Carroll - Plugging Contractor

C. H. Stough
District Conservation Agent

Date 1-10-53

PLUGGING
FILE SEC 22120-R-152
BOOK PAGE 67 LIST 2

RECEIVED
STATE CORPORATION COMMISSION
JAN 13 1953
CONSERVATION DIVISION
Wichita, Kansas

1-13-1953