

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
 Conservation Division
 800 Bitting Building
 Wichita, Kansas

FILE NO. 142-37LOCATION SE-SE-NWSEC. 22 TWP. 20 RGE. 15Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease J. G. SchmidtOperator Kans-Neb. Nat'l Gas Co. Inc. Address Hastings, NebraskaField _____ County BartonTotal Depth 3696' Feet. Plugging Contr. of m pipe pulling Co.
Lease no 11. St Bend Kans.

(Describe briefly the manner in which the well was plugged)

Surface pipe, 8 5/8" @ 690' CWC. Other casing was
5 1/2" @ 3763' with 200 5X cem. Top perf. was 3680'
Plugged back with cem. to 3696' filled. Hole back
with sand to 3675' and dumped 55X cem.
shot off and pulled 5 1/2" casing. Had out
Halliburton Cem. Co. and pumped in thru surface
casing 75 5X of fell mud plug and 100 5X of
cem. to complete plugging

Warren H. Horner
 District Conservation Agent

Date 11-24-53**PLUGGING**

FILE SEC 22 T 20 R 15 W
 BOX PAGE 142 LINE 37

CONDENSED

11-27-1953