

# WELL PLUGGING RECORD

## FORMATION PLUGGING RECORD

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittiny Building  
Wichita, Kansas

OR

Strike out upper line  
when reporting plug-  
ging off formations.

Barton County. Sec. 14 Twp. 20S Rge. (E) 15W (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines. Center SE $\frac{1}{4}$  NE $\frac{1}{2}$

Lease Owner. Gulf Oil Corporation

Lease Name. Effie Well No. 1

Office Address. Box 661, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole). Dry Hole

Date well completed. April 13 19 47

Application for plugging filed. April 18 19 47

Application for plugging approved. April 18 19 47

Plugging commenced. April 21 19 47

Plugging completed. April 24 19 47

Reason for abandonment of well or producing formation. Dry hole

If a producing well is abandoned, date of last production. --- 19 ---

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Name of Conservation Agent who supervised plugging of this well. H. W. Kerr

Producing formation. Arbuckle Depth to top. 3663' Bottom. --- Total Depth of Well. 3685' Feet

Show depth and thickness of all water, oil and gas formations. PB from 3740'


OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				5-1/2"	3738'	3050'
				8-5/8"	922'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pumped 10 sacks cement 3685'-3605'  
Filled with mud to 250'  
Spotted 15 sacks cement and mud to 20'  
Capped with 10 sacks cement



(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to. A. M. Bell Jr.  
Address. Box 661, Tulsa, Oklahoma

STATE OF Kansas, COUNTY OF Rice, ss.  
H. H. Wright (employee of owner) or (~~owner or operator~~) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) X H. H. Wright  
(Address) \_\_\_\_\_

SUBSCRIBED AND SWORN to before me this 25th day of April, 19 47

My commission expires May 18, 1950 Notary Public.

**PLUGGING**  
FILE SEC 14 T 20 R 15W  
BOOK PAGE 108 LINE 11

WELL NO. **1** LEASE **Effie** COMPANY **Gulf Oil Corporation & Amerada Oil Corp.** A.F.E. **3144**  
 DATE—DRILLING BEGAN **1-30-47** WELL COMPLETED **4-24-47** FIRST PRODUCTION **Plugged**  
 SAND RECORD **Arbuckle 3663'** TOTAL DEPTH **3685'**  
**P. B. from 3740'**  
 INITIAL PRODUCTION **DRY HOLE**

CASING RECORD

S—14 T—205 R—154

SIZE	WEIGHT	THD.	CLASS	MAKE	SET AT DEPTH	SACKS CEMENT	LBS. CAL. CHLO.	PULLED	LEFT IN
8-5/8	24	8R	A	L W	935'	463	75		935'
5-1/2	14	8R	A	Smile.	3738'	150		3050'	688'

Center			
St.			
M.			
Barren			
County			
Kansas			

Perforated 3662 - 84' with 88 holes.  
 Perforated 3683 - 91' with 43 holes.  
 Perforated 3699 - 3701' with 6 holes.  
 Acidized 3-2-47 with 2000 gallons.  
 Acidized 3-31-47 with 2000 gallons.  
 Acidized 4-5-47 with 5000 gallons.

ELEVATION — 1961'

Distance H: Top collar on 5-1/2" is 11' below rotary bushing.

FORMATION RECORD:

	From	To
Shale and sand	0	40
Shale, sand and shells		300
Sand and shale		595
Red rock		640
Shale and shells		765
Shale and red rock		930
Anhydrite		937
Anhydrite		960
Shale and shells		1795
Shale and lime		1995
Broken lime		2135
Lime		2245
Broken lime		2465
Shale and lime		3020
Lime		3605
Shale		3650
Lime		3686
Coring		3690
Lime (TOTAL DEPTH)		3740

ED  
5-13-47

WELL RECORD  
GULF T. 680-A 3-48  
15 009 05720 0000

WELL RECORD  
GULF T. 680-A 3-48  
15 009 05720 0000

**PLUGGING**  
FILE SEC 14 T 20 R 15W  
BOOK PAGE 108 LINE 11

STATE OF TEXAS  
MAY 16 1947