

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-23,201

LEASE NAME SMITH

WELL NUMBER 1

SPOT LOCATION S1/2 SE SW

SEC. 13 TWP 20 RGE. 15 (E) OR (W)

COUNTY BARTON

DATE WELL COMPLETED _____

PLUGGING COMMENCED 1-16-84

PLUGGING COMPLETED 1-31-84

TYPE OR PRINT

PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR ALLEN OIL CO.

ADDRESS BOX # 1389 GREAT BEND, KS. 67530

PHONE # (316) 793-5681 OPERATORS LICENSE NO. 5640

CHARACTER OF WELL OIL
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? YES

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? DIST. #6

IS ACO-1 FILED? _____ IF NOT, IS WELL LOG ATTACHED? NO

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM _____ T.D. 3670'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS | CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,393'

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET. PUT 4 SACKS OF CEMENT DOWN, SANDED BACK TO 3385' AND PUT DOWN 4 SACKS CEMENT. ALLIED CAME OUT AND PUMPED DOWN 4 HILLS; 5 GEL; 25 50/50 POZ MIX 4% GEL AND 3% C.C.; 5 GEL; 1/2 HILL; 40 50/50 POZ MIX; 4% GEL 3% C.C.; 5 GEL WIPER PLUG; 100 50/50 POZ MIX 4% GEL 3% C.C. TIME 2:00 P.M. MAX. PRESSURE 700LBS. SHUT IN SHUT IN AT 300 LBSS.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR H&H CASING PULLING CO. LICENSE No. 6053
ADDRESS FINEST MOBILE HOME PARK LOT 78 GREAT BEND, KS. 67530

STATE OF KANSAS COUNTY OF BARTON, SS.

DONALD H. HURST (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) Donald H. Hurst
FINEST MOBILE HOME PARK LOT 78
(ADDRESS) GREAT BEND, KS. 67530



SWORN TO BEFORE ME THIS 8th DAY OF February, 1984
Madeline Hurst
NOTARY PUBLIC

MY COMMISSION EXPIRES: _____

RECEIVED
STATE COMMISSION
FEB 14 1984
FORM CP-4
REVISED 06-83
CONSERVATION DIVISION
Wichita, Kansas