

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

WELL PLUGGING RECORD

API NUMBER 15-009-23,354-0000

LEASE NAME Dirks

WELL NUMBER 1

SPOT LOCATION SE SE SE

SEC. 13 TWP. 20 RGE. 15 (E) OR (W)

COUNTY Barton

DATE WELL COMPLETED 11-13-83

PLUGGING COMMENCED 11-14-83

PLUGGING COMPLETED 11-14-83

TYPE OR PRINT
PLEASE FILL OUT COMPLETELY
AND MAKE REQUIRED AFFIDAVIT.

LEASE OPERATOR Wes-Tech Energy, Inc.

ADDRESS R.R. #4, Box 101, Great Bend, Kansas 67530

PHONE # (316) 792-5653 OPERATORS LICENSE NO. 5591

CHARACTER OF WELL D&A
(OIL, GAS, D&A, SWD, INPUT, WATER SUPPLY WELL)

DID YOU NOTIFY THE KCC/KDHE JOINT DISTRICT OFFICE PRIOR TO PLUGGING THIS WELL? Yes

WHICH KCC/KDHE JOINT OFFICE DID YOU NOTIFY? Stafford, Kansas

IS ACO-1 FILED? Yes IF NOT, IS WELL LOG ATTACHED? _____

PRODUCING FORMATION _____ DEPTH TO TOP _____ BOTTOM T.D. 3680'

SHOW DEPTH AND THICKNESS OF ALL WATER, OIL AND GAS FORMATIONS.

OIL, GAS OR WATER RECORDS _____ CASING RECORD _____

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	900'	

DESCRIBE IN DETAIL THE MANNER IN WHICH THE WELL WAS PLUGGED, INDICATING WHERE THE MUD FLUID WAS PLACED AND THE METHOD OR METHODS USED IN INTRODUCING IT INTO THE HOLE. IF CEMENT OR OTHER PLUGS WERE USED STATE, THE CHARACTER OF SAME AND DEPTH PLACED, FROM FEET TO FEET EACH SET.

20 sx. @ 3590', 40 sx. @ 930', 75 sx. @ 300', 10 sx @ 40', 10 sx. in Rathole, 10 sx. in Mousehole, plugged with 165 sx. 50/50 Poz-mix, 3% CC, 4% Gel, plugged at 4:15 AM, 11-14-83, by Sun Oilwell Cementing

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

NAME OF PLUGGING CONTRACTOR Sun Oilwell Cementing LICENSE No. _____

ADDRESS P.O. Box 169, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Sedgwick, SS.

K.T. Woodman (EMPLOYEE OF OPERATOR) OR (OPERATOR) OF ABOVE-DESCRIBED WELL, BEING FIRST DULY SWORN ON OATH, SAYS: THAT I HAVE KNOWLEDGE OF THE FACTS, STATEMENTS, AND MATTERS HEREIN CONTAINED AND THE LOG OF THE ABOVE-DESCRIBED WELL AS FILED THAT THE SAME ARE TRUE AND CORRECT, SO HELP ME GOD.

(SIGNATURE) K.T. Woodman


(ADDRESS) 1022 Union Center, Wichita, KS

SUBSCRIBED AND SWORN TO BEFORE ME THIS 15th DAY OF November, 19 83

Kathryn A. Voigt
NOTARY PUBLIC

Kathryn A. Voigt

MY COMMISSION EXPIRES: April 20, 1985



RECEIVED
STATE CORPORATION COMMISSION FORM CP-4
NOV 17 1983 REVISED 06-83

CONSERVATION DIVISION
Wichita, Kansas

15.009.23354.0000

K. T. WOODMAN
REG. PHONE 733-0418
OFF. PHONE 265-7650
WICHITA, KANSAS

D. J. IANNITTI
PHONE 792-2921
GREAT BEND, KANSAS

WOODMAN & IANNITTI DRILLING COMPANY
Rotary Drilling Contractors

1022 UNION CENTER
150 N. MAIN
WICHITA, KANSAS 67202

November 15, 1983

Company:	Wes-Tech Energy, Inc.
Farm:	Dirks #1
Location:	SE SE SE
Section:	13-20S-15W
County:	Barton
Contractor:	Woodman & Iannitti Drilling Company
Total Depth:	3680'
Comm:	November 8, 1983
Comp:	November 14, 1983
Casing:	8-5/8" 24# & 20# set @ 900' w/450 sx. 60/40 Poz-mix, 3% CC, 2% Gel

Figures Indicate Bottom Formations:

100	Sand
307	Shale & Shells
420	Dakota Sand
550	Shale & Red Bed
886	Red Bed
900	Anhydrite
909	Anhydrite
1310	Shale & Red Bed
1846	Shale
2059	Shale
2340	Shale & Lime
2658	Shale & Lime
2925	Lime & Shale
3110	Lime & Shale
3268	Lime & Shale
3449	Lime
3547	Lime
3645	Lime Arbuckle
3680	Arbuckle

I certify the above to be a true and correct copy of the Drillers Log to the best of my knowledge and belief.

WOODMAN & IANNITTI DRILLING COMPANY

K.T. Woodman
K.T. Woodman, Partner

RECEIVED
STATE CORPORATION COMMISSION

NOV 17 1983

CONSERVATION DIVISION
Wichita, Kansas