

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Dakota Insurance Bldg.  
Wichita, Kansas

WELL PLUGGING RECORD

Barton County. Sec. 25 Twp. 20S Rge. (E) 15 (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE  
Lease Owner Raymond Oil Company, Inc.  
Lease Name BUMP Well No. I  
Office Address 410 Fourth National Bank Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed February 28, 19 60  
Application for plugging filed February 29 19 60  
Application for plugging approved February 29 19 60  
Plugging commenced February 29 19 60  
Plugging completed March 1 19 60  
Reason for abandonment of well or producing formation \_\_\_\_\_

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Donald Truan  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3735' Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Set bridge with 1/4 sack hulls on top at 600' and 20 sacks cement.

Filled hole to 180 feet with mud, set bridge with 1/4 sack hulls on top and 15 sacks cement. Filled hole to 40 feet with mud, set bridge and 10 sacks cement. 3 sacks cement in rat hole.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 1 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Raymond Oil Company, Inc.  
Address 410 Fourth National Bank Bldg., Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Rick P. Clinton (employer, operator or owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Rick P. Clinton  
410 Fourth National Bank Bldg., Wichita, Ks.  
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of March, 19 60

My commission expires May 13, 1962  
Mary Ellen Sampson Notary Public.



15.009.19435.0000

*RC*

Raymond Oil Company, Inc. #1 Bump  
SE SW SE, 25-20S-15W  
Barton County, Kansas

Elevation: 1914 GL  
1916 DF  
1918 KB

Contractor: Company Tools - Rig #1  
Commenced: February 17, 1960  
Completed: February 28, 1960

Casing Record:  
8-5/8" @ 602' w/350 sacks

Figures Indicate Bottom of Formation

<u>Formation</u>	<u>Depth</u>
Surface Hole	602
Shale w/ Shells & Red Bed	860
Anhydrite	880
Shale w/ Shells & Red Bed	1120
Shale & Shells	1700
Lime & Shale	1840
Lime with shale	1980
Lime & Shale	2795
Shale with Lime	2938
Lime with Shale	3236
Limestone	3560
Chert	3614
Sand	3637
Chert	3647
Dolomite	3735

D & A

TOPS:

Anhydrite	860
Topeka	2958
Heebner	3220
Toronto	3236
Douglas	3254
Brown Lime	3319
Lansing	3332
Conglomerate	3560
Simpson	3614
Arbuckle	3647
Rotary Total Depth	3735

**RECEIVED**  
STATE CORPORATION COMMISSION  
MAR 1 1 1960  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS    )  
                              ) SS  
COUNTY OF SEDGWICK )

I hereby certify that the above is true and correct to the best of my knowledge.

*Rick P. Clinton*  
Rick P. Clinton

Subscribed and sworn to before me this 3rd day of March, 1960

*Wanda E. Simpson*  
Notary Public

My Commission Expires: 5/13/62