

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Co. for Ag. Bldg. Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-009-23,473.0000

LEASE NAME Unruh

WELL NUMBER #1-25

2310 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 25 TWP 20 RGE. 15 (E) or (W)

COUNTY Barton

Date Well Completed _____

Plugging Commenced 2-14-89

Plugging Completed 3-1-89

LEASE OPERATOR Westech Energy Co., Inc.

ADDRESS Box 949, Great Bend, Kansas 67530

PHONE # (316) 792-5653 OPERATORS LICENSE NO. 5591

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? March 1, 1989

Which agent did you notify? Gilbert Scheck

Is ACO-1 filed? _____ If not, is well log attached? With application

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 3685'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8-5/8"	869'	None
				5-1/2"	3683'	2,852.15'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Dumped sand to 3600' and 5 sacks cement. Shot casing at 2800'. Pulled 72 joints of 5-1/2" casing. Allied plugged well with 500# hulls and 200 sacks 60/40 pozmix cement with 8% gel. Maximum pressure was 300 psi and shutin 100 psi.

Name of Plugging Contractor Rockhold Engineering, Inc. License No. 5111

Address Box 698, Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.

James W. Rockhold (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) James W. Rockhold

(Address) James W. Rockhold
Box 698, Gt. Bend, Ks. 67530

SUBSCRIBED AND SWORN TO before me this 21st day of March, 1989

Jona. M. Leatherman
Notary Public

My Commission Expires: _____
 IONA M. LEATHERMAN
 Barton County, Kansas
 My Appt. Exp. 9-26-91