

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-23,978.0000

LEASE NAME Unruh

WELL NUMBER B-1

2310 Ft. from S Section Lin

1980 Ft. from E Section Lin

SEC. 25 TWP. 20 RGE. 15 ~~X05~~ or (W

COUNTY Barton

Date Well Completed 7-8-85

Plugging Commenced 9-24-93

Plugging Completed 4:30 P.M.

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR WestTech Energy Co., Inc.

ADDRESS P.O. Box 889 Great Bend, Kansas 67530

PHONE#(316 792-5653) OPERATORS LICENSE NO. 5591

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-24-93 (date)

by Ken Kuhn (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top 3630 Bottom 3634 T.D. 3690

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	870	0
				5 1/2	3689	2713

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plugging materials were used, state the character of same and depth placed, from ___ feet to ___ feet each section.
Bottom plug: Sanded to 3580 & bailed 5 sx cement.

Top plug: Pulled 5 1/2 to 1702 & pumped 35 sx cement (60/40 w/8% gel), pulled up to 910 ft & pumped 45 sx cement, pulled to 692 & pumped 8 sx gel, pulled to 325 ft & circulated 75 sx cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WestTech Energy Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) WestTech Energy Co., Inc.

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and circumstances of the above-described well, as filed with the State Corporation Commission, and matters herein contained and the log of the above-described well, as filed with the State Corporation Commission, are true and correct, so help me God.

(Signature) Gary G. Burke, Pres

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 4 day of October, 19 93.



Anna K. Burke
Notary Public

Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1993
CONSERVATION DIVISION
Wichita, Kansas