

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,431-0000

LEASE NAME Brining

WELL NUMBER B-1

3390 Ft. from S Section Lin

1650 Ft. from E Section Lin

SEC. 25 TWP. 20 RGE. 15 (X) or (W)

COUNTY Barton

Date Well Completed 9-22-90

Plugging Commenced 9-23-93

Plugging Completed 3:30 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR WesTech Energy Co., Inc.

ADDRESS P.O. Box 889 Great Bend, Kansas 67530

PHONE# (316) 792-5653 OPERATORS LICENSE NO. 5591

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-23-93 (date)

by Marion Schmitt (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3626 Bottom 3632 T.D. 3632

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	871	0
				5 1/2	3626	2484

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each section. Bottom plug: Sanded to 3550 & bailed 5 sx cement.

Top plug: Pulled 5 1/2 casing to 1687 ft & pumped 35 sx cement (60/40 w/8% gel), pulled casing to 917 ft & pumped 45 sx cement, pulled to 688 & pumped 8 sx gel, pulled to 316 ft & circulated 75 sx cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WesTech Energy Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.

Gary G. Burke


(Employee of Operator) WesTech Energy Co., Inc.

above-described well, being first duly sworn on oath, says: That I have knowledge of the above-described well as plugged, and matters herein contained and the log of the above-described well as plugged, and the same are true and correct, so help me God.

(Signature) Gary G. Burke

(Address) Box 251, Great Bend, Kansas 67530

SUBSCRIBED AND SWORN TO before me this 4 day of October, 19 93



Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION

OCT 05 1993

CONSERVATION DIVISION
Wichita, Kansas