

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

WELL PLUGGING RECORD

Barton County, Sec. 25 Twp. 20 Rge. 15 (X) W (W)

Location as "NE/CNW/SW" or footage from lines: NE/4 SE/4 NW/4

Lease Owner Icer Addis

Lease Name Dueser Well No. 1

Office Address Box 8038 - Wichita, Kansas 67208

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 1-16 19 74

Application for plugging filed 1-16 19 74

Application for plugging approved 1-16 19 74

Plugging commenced 1-16 19 74

Plugging completed 1-16 19 74

Reason for abandonment of well or producing formation _____

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Donald Truan

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3643 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Hole full of heavy mud
Set Plug at 400' with 30 sacks cement thru drill pipe
Set Top Plug at 40' w/ 1/2 sk. hulls and 15 sacks cement
2 sacks in rat hole.

RECEIVED
STATE CORPORATION COMMISSION
JAN 18 1974
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use SACK of this sheet)

Name of Plugging Contractor Duke Drilling Co.

Address Box 823 - Great Bend, Ks. 67530

STATE OF Kansas COUNTY OF Barton, ss.

Leonard Williamson (employee of owner) or ~~XXXXXX~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard Williamson

Box 823 - Great Bend, Kansas 67530
(Address)

SUBSCRIBED AND SWORN to before me this 17 day of January, 19 74

My commission expires April 11, 1974 Verity M. Hague Notary Public.

WELL LOG

DATE COMMENCED: January 7, 1974
 DATE COMPLETED: January 16, 1974

Icer Addis
 DUESER #1
 NE/4 SE/4 NW/4
 Sec. 25-T20s-R15W
 Barton County, Kansas 67530

0 - 60'	Sand
60 - 300'	Shale
300 - 450'	Sand
450 - 876'	Red Bed
876 - 890'	Anhydrite
890 - 1300'	Red Bed
1300 - 1750'	Shale & Sand
1750 - 3218'	Shale & Lime
3218 - 3222'	Shale
3222 - 3234'	Lime & Shale
3234 - 3251'	Lime
3251 - 3318'	Shale
3318 - 3331'	Lime & Shale
3331 - 3629'	Lime, Shale, Chert, Sand
3629 - 3643'	Dolomite
3643'	RTD

ELEVATION: 1917 K.B.

FORMATION DATA

ANHYDRITE	876
HEEBNER	3218
TORONTO	3234
DOUGLAS	3251
BR. LIME	3318
KANSAS CITY	3331
AREUCKLE	3629
RTD	3643

SURFACE PIPE: Set 876' of
 8-5/8", 20# surface pipe with
 250 sks. 2% Gel, 2% C.C. 50/50
 pozmix and 200 sks. common cement,
 3% CC.

AFFIDAVIT

STATE OF KANSAS
 COUNTY OF BARTON) ss.

Leonard Williamson, of lawful age, does swear and state that the facts and statements herein contained are true and correct to the best of his knowledge.

Leonard Williamson

Subscribed and sworn to before me this 17th day of January 1974.

Maureen M. Hogue
 Notary Public

My Comm. Expires: April 11, 1974

RECEIVED
 STATE CORPORATION COMMISSION
 JAN 18 1974
 CONSERVATION DIVISION
 Wichita, Kansas