

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-009-24,180.0000

LEASE NAME Dueser - French

WELL NUMBER B-1

2970 Ft. from S Section Lin

2970 Ft. from E Section Lin

SEC. 25 TWP. 20 RGE. 15 XX or (W)

COUNTY Barton

Date Well Completed 9-1-86

Plugging Commenced 9-22-93

Plugging Completed 12:00 PM

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR WesTech Energy Co., Inc.

ADDRESS P.O. Box 889 Great Bend, Kansas 67530

PHONE# (316) 792-5653 OPERATORS LICENSE NO. 5591

Character of Well Inj.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 9-22-93 (date)
by Ken Kuhn (KCC District Agent's Name)

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Arbuckle Depth to Top 3632 Bottom 3634 T.D. 3690

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	875	0
				5 1/2	3688	2009

Describe in detail the manner in which the well was plugged, indicating where the mud fluid placed and the method or methods used in introducing it into the hole. If cement or other p were used, state the character of same and depth placed, from ___ feet to ___ feet each s
Bottom plug: Sand to 3580 & bailed 5 sx cement.

Top plug: Pull casing to 1700 & spot 35 sx (60/40 w/8% gel); Pull pipe to 900 ft & spot 45 sx cement, pull up to 700 ft & spot 8 sx gel, pull up to 325 ft & circulate 75 sx cement to surface.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Great Bend Casing Pullers, Inc. License No. 4635 CP

Address Box 251, Great Bend, Kansas 67530

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: WesTech energy Co., Inc.

STATE OF Kansas COUNTY OF Barton, ss.


Gary G. Burke

(Employee of Operator WesTech Energy Co., Inc.)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts stated in the above statements, and matters herein contained and the log of the above-described well as filed in the same are true and correct, so help me God.

(Signature) Gary G. Burke Pres

(Address) Box 251, Great Bend, Kansas 67530



SUBSCRIBED AND SWORN TO before me this 4 day of October, 19 93.

Anna K. Burke
Notary Public

My Commission Expires: 4-30-96

RECEIVED
STATE CORPORATION COMMISSION
OCT 05 1993
CONSERVATION DIVISION
Wichita, Kansas