

KANSAS

FORM CP-3
Rev. 5-5-81

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT REPORT

API Number 15-009-22,398.0000

200 Colorado Derby Bldg.
Wichita, KS 67202

Operator's Full Name Rockwood Petroleum Company

Complete Address 815 Douglas Bldg., Wichita, Kansas 67202

Lease Name Neff Well No. 1

Location NW SW NE Sec. 22 Twp. 20 Rge. 14 (~~EAST~~) (West)

County Barton Total Depth 3600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Duke Drilling Co., Inc. and Allied Cementing Co., Inc.

Address Box 823, Great Bend, Kansas License No. _____

Operation Completed: Hour: 2:00 PM Day: 13 Month: June Year: 19 81

Plugging Operations attended by Agent? All Part _____ None _____

The above well was plugged as follows: 8-5/8"-829'-425 sacks circ.
Top Anhydrite 826'

Hole circulated and filled with mud. 30 sacks cement pumped through

drill pipe at 835'. 30 sacks cement pumped through drill pipe at 200'.

Plug and 1/2 sack hulls pushed to 40' and hole cemented to base of cellar

with 10 sacks cement. Rathole cemented with 10 sacks cement.

Cement used: 50-50 Pozmix w/4% gel and 3% Cal. Chloride

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above well was plugged as herein stated

Signed: [Signature]
Conservation Division Agent

INVOICED

DATE 7-27-81

INV. NO. 6029-W