

## DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
 Conservation Division  
 211 North Broadway  
 Wichita, Kansas

FILE NO. 13-35  
 LOCATION NW Corner  
 SEC. 21 TWP. 20 RCE. 14 W

Dry Hole \_\_\_\_\_ Abandoned Oil Well  Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Unruh  
 Operator E. H. Adair Address 407 W-K-H Bldg. Wichita Ks.  
 Field \_\_\_\_\_ County Barton  
 Total Depth 3260 Feet.  
 Plugging Contractor Ace Pipe Pulling Co  
 Plugging Contractor's License No. # 2  
 Address Great Bend Kansas

(Describe briefly the manner in which the well was plugged)

Surface pipe 8 3/4" @ 863' C.W.C. 4 1/2" casing set.  
3620' w/ 100 sx Cem. Cement drilled out to  
3610' top perf 3578'. Filled back with Chat  
to 3565' dumped 3 sx Cem. Shot off and  
pulled 4 1/2" casing. Filled hole with mud to  
300' set rock bridge and dumped 20 sx Cem.  
mud to 35' rock bridge and 10 sx Cem. to base of  
cellar.

3-21-1955

RECEIVED  
 STATE CORPORATION COMMISSION

MAR 21 1955

CONSERVATION DIVISION  
 WICHITA, KANSAS

Warren H. Garner  
 District Conservation Agent

Date March 18, 1955

