

8

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission
Conservation Division
800 Bitting Building
Wichita, Kansas

FILE NO. 50-35

LOCATION CNE-NWSE

SEC. 20 TWP. 20 RGE. 14

Dry Hole _____ Abandoned Oil Well _____ Abandoned Gas Well X

I have today completed supervision of plugging of:

Well No: 1 Lease W. T. Smith

Operator Math. Co. of Refinery, Okla. Address #820 - W. N. Bldg. Wichita - Kans

Field _____ County Butler

Total Depth 2644 Feet.

(Describe briefly the manner in which the well was plugged)

Surface Pipe 8 1/2" - 860 ft. Circulated with cement
5 1/2" casing at 2644 ft. Plugged back to 2560 ft
with gravel. Dumped 5 sacks of cement at 2560 ft.
3/4 casing cemented with 700 sacks cement. Shot off
& pulled the 5 1/2 casing. Mud to 250 ft. Set
Rock Bridge & 13 sacks of cement at 250 ft.
Mud to 30 ft. Plug & 10 sacks cement at the surface
Standard Casing Pulling Co. Plugging Contractors

STATE CORPORATION COMMISSION

JAN X 9 1951

CONSERVATION DIVISION
Wichita, Kansas

C. M. Stoenek
District Conservation Agent

Date 1-6-51

PLUGGING
FILE SEC 20 T 20 R 14
BOOK PAGE 50 LINE 35