

DISTRICT CONSERVATION AGENT'S REPORT

*R*

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 13-36

LOCATION SW-NE-NE

SEC. 20 TWP. 20 RGE. 14W

Dry Hole      <sup>*Sw*</sup> Abandoned Oil Well  Abandoned Gas Well     

I have this date completed supervision of plugging of:

Well No. 1 Lease Smith

Operator E.H. Adair Address 407 W-K-H Bldg. Wichita Kans.

Field      County Barton

Total Depth 3622 Feet.

Plugging Contractor E.H. Adair

Plugging Contractor's License No. 207

Address 407 W-K-H Bldg. Wichita Kans

(Describe briefly the manner in which the well was plugged)

*S. Pipe 8 5/8" @ 667 c.w.c. 5 1/2" @ 3580 w/ 100 sk Cem  
Filled back with sand to 3570 and dumped  
5 sk of Cem. Shot off and started 5 1/2" casing.  
Mudded with 35 sk of fresh full mud.  
Pulled 5 1/2" casing. Pumped plug and 130 sk  
of Cem. Filling surface casing from approx 390'  
to base of cellar with Cem. By Halliburton Com. Co.*

RECEIVED  
STATE COMMISSION  
MAR 6 - 1954  
PLUGGING  
FILE SEC 20 TWP 20 RGE 14W  
BOOK PAGE 13 LINES 36  
CONSERVATION DIVISION  
Wichita, Kansas

Warren H. Horner  
District Conservation Agent

Date Mar 4, 1954

3-6-1954