

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

FEB 27 1967

CONSERVATION DIVISION
WICHITA, KANSASJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued February 21, 1967.Operator's Full Name Cities Service Oil CompanyComplete Address: Box 308, Great Bend, KansasLease Name Booth "B" Well No. # 1Location App. C SE NW Sec. 30 Twp. 30 Rge. 17 (E) (W) WCounty Kiowa Total Depth 5076'Abandoned Oil Well Gas Well Input Well SWD Well D & A XOther well as hereafter indicated: Plugging Contractor: Knight Casing Pulling CompanyAddress: Box 405, Chase, Kansas License No. 436Operation Completed: Hour 11:30AM Day 25th Month Feb. Year 1967

The Above well was plugged as follows:

994' of 8 5/8" surface pipe, cement circulated. 5074' of 4 1/2" long string,
cemented with 125 sacks. This is an open hole. Bottom of the hole was
squeezed with 125 sacks, bringing the top of the cement to 4800' in the
4 1/2". 1900' of 4 1/2" long string was recovered from the hole. Fluid level
in the hole was at 325', bridge plug and rock bridge from 325' to 315',
and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge
from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Audie Elving
Well Plugging SupervisorDATE 2/27/67INV. NO. 4834-W