

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

MAR 19 1975

CONSERVATION DIVISION  
Wichita, Kansas

3-19-1975

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

Operator's Full Name Dunbar Drilling, Inc.

Complete Address 5252 North Broadway, Wichita, Kansas 67219

Lease Name Glenn Well No. 1

Location C NE SE Sec. 3 Twp. 20 Rge. (E) (W) 19

County Pawnee Total Depth 4157'

Abandoned Oil Well XX Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated     

Plugging Contractor      Co. Tools     

Address      License No. 709

Operation Completed: Hour 2:PM Day 17 Month 3 Year 1975

The above well was plugged as follows:

Total Depth 4157' 8 5/8 csg set at 404' cwc: 250 sx.

5 1/2 csg set 4156' cw 125 sx cem.

5 1/2 csg pbsd 4076' & perf. (4076-4053)

Filled 5 1/2 csg with sand (4076-4000) dumped 5 sk cem W/dump bailer. (4000-3965)

Cutoff & recovered 2150' of 5 1/2 csg.

Pumped down 8 5/8 csg with 15 sk gel & water W/100 lbs hulls -released 8 5/8 plug

& pumped 80 sk cem -displaced with 6 sk gel & water & capped with 20 sk cem.

by Allied Cementing Co. PP 400 lbs. SIP 300 lbs.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 3/20/75

INV. NO. 1017-W