

KANSAS

R

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts,  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 25 1968  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Imperial Oil Company  
Complete Address: Box 784, Great Bend, Kansas 67530  
Lease Name Caskey Well No. # 1  
Location NW NW NW Sec. 1 Twp. 20 Rge. 14 (E) (W) X  
County Barton Total Depth 3555  
Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A       
Other well as hereafter indicated:       
Plugging Contractor: Southwest Casing Pulling Company, Inc.  
Address: Box 364, Great Bend, Kansas License No. # 399  
Operation Completed: Hour 4:30 PM Day 20 Month 6 Year 1968

The Above well was plugged as follows:

13" 128' Cwc. 8 5/8" 785' Cwc.  
Sanded hole back to 3300' & dumped 4 sax cement with dump bailer. Pulled pipe.  
Mudded hole to 370', set 20' rock bridge, & displaced 5 yds. Ready-mix cement,  
cementing from 350' to base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Don L. Linn  
Well Plugging Supervisor

DATE 6-25-68

INV. NO. 7997-W