

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 009 - 21546.0000 (of this well)

Operator's Full Name Rockies Oil & Gas

Complete Address Box 8929 Midland, Texas 79703

Lease Name City of Great Bend, Kans. Well No. C-1

Location C N/2 NW Sec. 3 Twp. 20 Rge. 14 (EX) (W) X

County Barton Total Depth 2332'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Pawnee Well Service, Inc.

Address 1019 Taft Great Bend, Kansas 67530 License No. 633

Operation Completed: Hour 2:15 PM Day 19 Month 2 Year 1979

The above well was plugged as follows:

Sanded back to 2250' and 4 sx cement with dump bailer.

Squeezed thru 8 5/8" surface casing with 3 sx hulls,

20 sx mud gel, plug and 125 sx cement.

Max pres 800# Shut in pres 450#.

Recovered 1830' of 4 1/2" casing.

Plugged back to 2298'. Top perforation at 2286'.

2328' of 4 1/2" casing cemented with 100 sx cement.

305' of 8 5/8" surface casing cement circ.

I hereby certify that the above well was plugged as herein stated.

RECEIVED
STATE CORPORATION COMMISSION

Signed: Deane Rankin
Well Plugging Supervisor

INVOICED
FEB 22 1979

DATE 2-27-79
INV. NO. 9163-W
CONSERVATION DIVISION
Wichita, Kansas