

State of Kansas



FORM - CP-2
Rev. 6-26-62

15.009-01564.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

JUN 29 1964

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Frank Musgrove of Hellar Drilling Co., Inc. has this date requested permission to plug the following described well:

Mr. D. L. Hellar guarantees payment of the plugging fee.

Operator's full Name: Hellar Drilling Co., Inc. & Geo. Grenyo

Complete Address: 1014 Union Center, Wichita, Kansas

Lease Name: Caskey Well No. # 1

Location: SW SE NE Sec. 1 Twp. 20 Rge. 14 (E) (W) W

County Barton Total Depth 3542 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Frank Musgrove was instructed to plug the well as follows:

8 5/8" 401' Cwc.

Filled hole with heavy mud to 275'; set plug with 1/4 sax
hulls; displaced 25 sax cement thru drill pipe. Mud to 40';
1/2 sax hulls; plug & displaced 10 sax cement, cementing
to base of cellar.

Very truly yours,

Don Truman