



15.009.21876.0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

245 North Water

WICHITA, KANSAS 67202

July 25, 1980

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG - 5 1980

CONSERVATION DIVISION
Wichita, Kansas

8-5-1980

J. Lewis Brock
Administrator
245 North Water
Wichita, Kansas 67202

Dear Sir:

Mr. Leonard Williamson of Duke Drilling Co. has this
date requested permission to plug the following described well:

Mr. Williamson guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: One Main Place, Suite 900, Wichita, Kansas 67202

Lease Name: Merten Well No. 1

Location: SE SE SW Sec. 1 Twp. 20 Rge. 14 (W) X

County: Barton Total Depth 3550' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Williamson was instructed to plug the well as follows:

8 5/8" - 783' Cem. Circ. Fill hole with mud. Pump 25 sacks
Cement through drill pipe at 775'. Pump 25 sacks cement
through drill pipe at 300'. Fill hole with mud to 40'.
Push plug and 1/2 sack hulls to 40' and cap hole with
10 sacks cement. Cement rat hole with 5 sacks cement.

Very truly yours,

William J. Larson
Conservation Division Agent